



## ADDENDUM NO. 1

**DATE:** April 22, 2024

**PROJECT:** Rawlinson Road Middle School Drainageway Erosion Repairs

**OWNER:** Rock Hill Schools

**ENGINEER:** Campco Engineering, Inc.

**CE#:** 9778-E

**TO:** All Plan Holders of Record

---

This Addendum becomes a part of the Contract Documents and modifies the original Contract Documents dated March 6, 2024. Addendum shall be provided to all plan holders of record in the manner that original Contract Documents were received. All bidders shall acknowledge receipt of this Addendum in the Bid Proposal Forms.

**PROJECT MANUAL REVISIONS/ADDITIONS** - None

**PLAN REVISIONS/ADDITIONS** - None

### **CLARIFICATIONS**

The following responses are to the questions submitted to the architect:

**Question 1:** Can mulch from clearing debris be spread on-site?

**Response:** *Yes, mulch can be placed in locations on-site to be identified by the Owner. The mulch shall be spread and not stock-piled.*

**Question 2:** If an additional construction entrance is install, could contractor enter the site off of Quite Acres Road to access the work behind the softball field? The purpose would be to lessen the damage done by accessing the area with dump trucks from the entrance at the traffic circle as shown on the plans.

**Response:** *The project plans approved by the City of Rock Hill do not include a construction access from Quiet Acres Road. The contractor may request approval to install the construction entrance from the City of Rock Hill at the pre-construction conference.*

**Question 3:** The trees listed in the planting chart of sheet L1.2, indicate the trees 0by7.8 7( )-16(of)4( )-28(sh(n )-17

**Question 4:** It was mentioned in the pre-bid meeting by the engineer that bid item#4, (excess earthwork) would be quantified by truck counts. What will the quantity (cy) per truck be?

**Response:** *The quantity will be measured based on the capacity of the truck being used.*

**Question 5:** Did Rock Hill Schools identify a location to place excess earthwork material?

**Response:** *No, all excess earthwork material shall be removed from the project site and disposed at an approved location identified by the Contractor.*

**END OF ADDENDUM NO. 1**

Submitted by,  
Campco Engineering, Inc.



J. Michael Fry, PE

cc: Brian Vaughan, Assistant Superintendent of Operations – Rock Hill Schools  
Lee Faris, Procurement Specialist – Rock Hill Schools